

# **Commissioning Checklist – Step-by-Step Guide**

*For Cryogenic Nitrogen Plants*

*By Satya Cryogenic Consulting*

# Introduction

Commissioning is the bridge between construction and full-scale operation — the stage where a nitrogen plant truly comes to life.

This guide provides a clear, step-by-step framework to ensure a safe, efficient, and error-free startup process.

Developed from real on-site experience, it's ideal for:

- Plant commissioning engineers
- Operators and maintenance teams
- Engineering students and industrial trainees

# Section 1:

## Pre-Commissioning Checklist

**Objective:** Ensure all systems are ready before introducing cryogenic fluids.

| # | Item  | Verification Notes |
|---|---|--------------------|
|   | 1. Mechanical completion of all systems.<br>(no leaks, flanges tightened)   |                    |
|   | 2. Liquidation of Punch list  |                    |
|   | 3. Verify as per P&ID <ul style="list-style-type: none"><li>• Erection / Installation of Equipment, Piping, and Instruments etc.</li><li>• Correct locations of all Instruments.</li><li>• Correct directions of check valves, globe valves, flow orifice, strainers, control valves etc.</li></ul> |                    |

| #   | Item  | Verification<br>Notes |
|-----|---|-----------------------|
| 4.  | Piping insulation, and supports verified as per design.   |                       |
| 5.  | Carry out Internal Inspection of Equipment  |                       |
| 6.  | Electrical & Instrumentation: <ul style="list-style-type: none"><li data-bbox="375 846 1122 951">• Verify Instruments calibrated and signal tested.</li><li data-bbox="375 972 1081 1077">• Control system loop tested and interlocks verified.</li><li data-bbox="375 1098 980 1203">• Electrical connections and earthing verified.</li></ul> |                       |
| 7.  | Safety relief valves tested and tagged.   |                       |
| 8.  | Check for Purification / drying system  |                       |
| 9.  | Purging and drying sequence ready.  |                       |
| 10. | Calibration of analyzers.   |                       |

| #   | Item   | Verification<br>Notes |
|-----|--|-----------------------|
| 11. | No Load Run of Motors.   |                       |
| 12. | Adsorbent charging   |                       |
| 13. | Lubricant charging.  |                       |
| 14. | Carry out Water flushing / Air blowing of piping.  |                       |
| 15. | Conduct Leak checks of systems after flushing & blowing, including inside cold box piping & Equipment. |                       |

# **Section 2:**

## **Commissioning Checklist**

Each phase should be completed in sequence to avoid process disruptions or damage.

### **Phase 1: System Purging & Leak Test**

- Verify all lines are clean and dry.
- Conduct pressure test with inert gas (typically nitrogen).
- Apply soap solution or detector to check for leaks.
- Ensure proper venting before next step.
- Nitrogen purging of Cold box Insulation.

### **Phase 2: Utilities Charging**

- Electrical charging
- Instrument air
- Cooling water

### **Phase 3: Cooling Down Process**

- Do cooling down gradually to avoid thermal shock.
- Monitor temperature gradients.

- Check expansion joints and cold box integrity.
- Record cooling duration and steady-state time.

#### **Phase 4: Product Gas Stabilization**

- Maintain design flow and temperature.
- Measure product gas purity and dew point.
- Adjust air separation or distillation parameters as needed.

#### **Phase 5: Storage & Transfer System**

- Verify storage tank insulation and pressure buildup.
- Check valves, level gauges, and vent lines.
- Ensure transfer lines are cooled before operation.

## **Section 3:**

# **Safety Guidelines**

Safety during commissioning is non-negotiable. Always follow plant-specific SOPs and ensure all personnel are trained.

### **Safety Checklist:**

- No oil / grease spillage in nearby area
- PPE worn (cryogenic gloves, face shield, jacket, safety shoes)
- Oxygen monitoring system active
- Pressure vessels certified and vented properly
- No unauthorized personnel in the zone
- Emergency isolation valves accessible

## **Section 4:**

# **Conclusion**

A well-commissioned nitrogen plant ensures efficiency, safety, and long-term reliability.

This checklist serves as both a guide and a record of professional commissioning practices.

### **Next in Series:**

- *Troubleshooting eBook – Solve Common Plant Issues*
- *Mini Course – Nitrogen Plant Commissioning & Safety*

For more resources, visit **Satya Cryogenic Consulting**.

---